



**installation guide**



Consistent with Arxx Building Product's policy of continued research and development, we reserve the right to modify or update the information contained in this or any other material published by Arxx Building Products. The onus remains on the user of Arxx™ Wallsystems to obtain the most recent information available.

The most recent version of the Arxx Installation Manual is available on the Arxx Web site at [www.arxxbuild.com](http://www.arxxbuild.com).

Because Arxx Building Products has no control over installation, workmanship, accessory materials or conditions of application, no responsibility or expressed or implied warranty, either as to merchantability or fitness for a particular purpose, is made as to the performance or results of an installation using Arxx Wallsystems, except that the physical characteristics of Arxx Wallsystems shall meet or exceed the specifications published by Arxx Building Products.

Arxx High Performance Wallsystems and any other marks, drawings, or symbols identifying products and/or services of Arxx Building Products are trademarks of Arxx Building Products.

## > BUILDING SOLUTIONS

## > BUILDING TRUST

### Who Are We?

We're a company built on trust — product trust, people trust. Building Trust. We've made a commitment to offer you reliable, cost-effective solutions for all your building challenges. Arxx™ helps build better communities, for better living. That's why we're the preferred choice of leading construction professionals.

### What is the Arxx High Performance Wallsystem?

Our wallsystem is a simple solution to all your building projects, no matter how complex. Arxx interlocking, light-weight expanded polystyrene concrete forms are designed to remain as a permanent part of the wall after the concrete is placed. The insulating capacity of expanded polystyrene coupled with the structural integrity of reinforced concrete is a powerful combination: Arxx walls are stronger, safer, quieter and more energy-efficient.

### People to People

At Arxx, we put people first. We know you look to us for solutions; that's why we make sure you have the technical customer support you need. Our accessible and talented network of designers, engineers, technical customer support, distributors, installers and product trainers are ready to assist you with your building challenges.

### Technical Support

Our experienced technical customer support team is ready to help you with the special challenges of your building projects – no matter how large or small, how simple or complex. Our regional sales team is prepared to coordinate with local distributors and your construction team to provide additional support – if and when you need it.

❖ You can reach Technical Support at 1-800-293-3210 between 8:00 am and 5:00 pm Eastern.

### Training

Arxx offers a variety of training programs that include in-class instruction as well as in-field inspections of work in progress. We offer our in-class training programs on a regular basis, year round, at locations throughout North America.

Arxx also has available, upon request, training videos.

❖ You can inquire about Training by calling 1.800.293.3210.

# PREFACE

---

## Arxx™ Website and Email

The website is updated regularly with additional product documentation, Technical Bulletins and Arxx Newsletters.

This installation Guide and other Arxx published documentation is posted on the website.

❖ Arxx website – [www.arxxbuild.com](http://www.arxxbuild.com)

❖ You can email inquires to Arxx – [info@arxxbuild.com](mailto:info@arxxbuild.com)

## Installation Guide Comments

In an effort to keep this guide as accurate and user friendly as possible, we encourage you to submit comments on the information contained herein. Your comments will be reviewed prior to the next printing.

❖ Email comments to – [installguide@arxxbuild.com](mailto:installguide@arxxbuild.com)

## Arxx Wallsystems Icons

The following icons are used throughout the guide to highlight specific information:



**USING AND GETTING THE MOST OUT OF ARXX – REFER TO THIS SYMBOL FOR IMPORTANT INFORMATION AND TIPS.**



**BUILDING CODES, MATERIAL STANDARDS OR REGULATIONS – REFER TO THIS SYMBOL FOR INFORMATION AND REFERENCES.**



**BUILDING AND WORK-SITE SAFETY – REFER TO THIS SYMBOL FOR SAFETY INFORMATION AND TIPS.**



**BEST PRACTICE – REFER TO THIS SYMBOL FOR SUGGESTED BEST PRACTICE GUIDES. THESE ARE OFFERED AS SUGGESTIONS ALTHOUGH SOME MAY BE REQUIRED BY LOCAL BUILDING CODES.**



**RECYCLING – REFER TO THIS SYMBOL FOR RECYCLING INFORMATION AND TIPS.**

# CONTENTS

---

<b>1</b>	<b>Arxx™ Wallsystems Installation</b>	<b>1</b>
1.1	GETTING STARTED	2
1.1.1	Tools, Equipment and Project Planning	2
1.1.2	Footings/Slabs On Grade (SOG)	2
1.1.3	Wall Layout	4
1.1.4	Material Placement	5
1.1.5	Course Placement	8
1.1.6	Transitions Between 4", 6", 8" and 10" Forms	10
1.2	FORM UNITS	11
1.2.1	Standard Form Units	12
1.2.2	Corner Form Units	13
1.2.3	Adjustable Corner Form Units	14
1.2.4	Fixed 45° Form Units	16
1.2.5	Extended Brick Ledge Form Units	17
1.2.6	Tapered Top Form Unit	20
1.2.7	Buried Web Form Units	21
1.2.8	Height Adjusters	22
1.2.9	End Caps	23
1.3	GRADE BEAMS	24
1.4	TEE-WALLS	25
1.5	REINFORCEMENT	26
1.5.1	Fundamentals of Reinforcing	26
1.5.2	Splices in Reinforcing Steel	26
1.5.3	Horizontal Reinforcing	27
1.5.4	Vertical Reinforcing	29
1.6	DOOR AND WINDOW OPENINGS	31
1.6.1	Buck Saver™	31
1.6.1.1	Buck Saver Installation	32
1.6.1.2	Window Installations	34
1.6.1.3	Radius Top Openings	35
1.6.1.4	Door Installations	35
1.6.1.5	Buck Saver with Stucco Installation	37
1.6.1.6	Ultraviolet Protection for Buck Saver	37
1.6.1.7	Canadian Standards	38
1.6.1.8	American Standards	38
1.6.1.9	General Notes	39
1.6.2	Wood Bucks	41
1.6.2.1	Wood Buck Installation	42
1.6.3	Window and Door Buck Material Options	44
1.7	REINFORCEMENT AT OPENINGS	45

## CONTENTS

---

1.8	WALL ALIGNMENT	46
1.9	SERVICE PENETRATIONS & BEAM POCKETS	47
1.10	PRIOR TO PLACEMENT OF CONCRETE	48
1.10.1	Pre-Placement Checklist	49
1.11	CONDITIONS AFFECTING CONCRETE MIX	50
1.12	CONCRETE PLACEMENT	52
1.13	CONSOLIDATION OF CONCRETE	53
1.14	COMPLETION OF CONCRETE PLACEMENT	54
1.15	POST-PLACEMENT CHECKLIST	55
1.16	ABOVE GRADE WALLS	56
1.17	BELOW GRADE MOISTURE PROTECTION	57
1.17.1	Overview	57
1.17.2	Arxx™ Waterproofing Membrane	57
1.17.2.1	Arxx Waterproofing Membrane Installation	58
1.17.2.2	Precautions for Cold & Hot Weather Application	60
1.17.3	The Maxx™ Foundation Wrap with Delta®-MS Technology	61
1.17.3.1	The Maxx Foundation Wrap Installation	62
1.17.3.2	Sealing the Flat Tab	68
1.17.3.3	Installing Mold Strip	68
1.17.3.4	Service Penetration	69
1.17.3.5	Windows & Openings	69
1.17.3.6	Slopes & Vertical Terminations	69
1.17.3.7	Extended Brick Ledge Detailing	70
1.17.3.8	Repairs	70
1.17.3.9	Clean-up and Inspection	71
1.17.4	Polyguard® 650 XT Waterproofing Membrane with Termite Barrier	71
1.17.4.1	Polyguard® 650 XTM Membrane Installation	72
1.17.4.2	Polyguard® 650 XTP Membrane Installation	72
1.17.5	Parging (Cementitious Coating)	73
<b>2</b>	<b>Interior Finishes</b>	<b>77</b>
2.1	GYPSUM BOARD (DRYWALL®)	78
2.1.1	Corner Attachment	78
2.2	PANELING	79
2.3	OTHER INTERIOR FINISHES	80
<b>3</b>	<b>Exterior Finishes</b>	<b>83</b>
3.1	ULTRAVIOLET RAYS	84
3.2	IMPACT NAILERS	85
3.3	EIFS	86
3.4	TRADITIONAL (CEMENT ) STUCCO	87



---

3.5	MASONRY VENEER	88
3.5.1	Tapered Top Form	88
3.5.2	Extended Brick Ledge	89
3.6	SIDING	91
3.7	OTHER EXTERIOR FINISHES	92

## **4 Special Applications 95**

4.1	WOOD FLOOR CONNECTIONS	96
4.1.1	Conventional Platform Framing	96
4.1.2	Embedded Floor Joist Assembly	98
4.1.3	Ledger Board (Rim Joist) Floor Connection Assembly	99
4.1.3.1	Anchor Bolt Connection System	99
4.1.3.2	Ledger Connector System	101
4.1.4	Extended Brick Ledge Floor Support Assembly	104
4.2	CONCRETE FLOORS	105
4.2.1	Hambro® Composite Concrete Floors	105
4.2.2	Composite Steel Deck	106
4.2.3	Pre-Cast Concrete Slab (Hollow Core)	108
4.3	GABLE ENDS	110
4.3.1	Typical Gable Framing	110
4.3.2	Alternate Gable Framing	110
4.4	CHIMNEYS	111
4.5	ROOF CONNECTIONS	112
4.5.1	Rafter or Truss Roof Connection	112
4.5.2	Flat Roof Connection	114
4.6	CABINETS AND OTHER HEAVY ITEMS	115

## **5 Utility Installations 117**

5.1	ELECTRICAL	118
5.1.1	Prior to Concrete Placement	118
5.1.2	After Concrete Placement	119
5.2	PLUMBING/PIPING/MECHANICAL	122
5.2.1	Prior to Concrete Placement	122
5.2.2	After Concrete Placement	123

## **6 Vapor Barrier/Air Barrier 125**

6.1	INTRODUCTION	126
6.2	VAPOR BARRIER	127
6.3	AIR BARRIER	128

## CONTENTS

---

<b>7</b>	<b>Arxx™ Alignment Systems</b>	<b>131</b>
7.1	ARXX ALIGNMENT SYSTEMS	132
7.1.1	Product Overview	132
7.1.2	Relevant Codes and Standards	132
7.1.3	R-100 Alignment System	133
7.1.4	C-120 Alignment System	134
7.1.5	C-144 Alignment System	135
7.1.6	Installation	136
7.1.7	Installation of the Arxx Alignment Systems	136
7.1.8	Installation of the Scaffold	137
7.1.9	Installation of the Guardrail	137
7.1.10	Wind Resistance	137
7.1.11	Brace Pole: Installation Limitations	137
7.1.12	Limitations of the Scaffold	137
7.1.13	Anchor Requirements	138
7.1.14	Post Concrete Placement	142
7.2	BMAS	143
7.2.1	Wall Alignment	143
7.2.2	Scaffolding Assembly	147
7.3	TMAS	149
7.3.1	TMAS Overview	149
7.3.2	TMAS Installation	150
7.3.3	Scaffolding Assembly	156
7.4	ARXX TALL WALL BRACING	158
7.4.1	Arxx System Scaffold™	158
7.4.2	Arxx Leading Edge™	158
7.4.3	Alternate Bracing Method	158

## Appendix A

COMMON QUESTIONS	161
------------------	-----

## Appendix B

GLOSSARY	165
----------	-----

## Appendix C

REFERENCES	169
------------	-----



---

## Appendix D

TERMITE TREATMENT AND PROTECTION	173
BACKGROUND	174
TREATMENT AND PREVENTION	175
RECOMMENDATIONS & SUGGESTIONS	176

## Appendix E

ESTIMATING	179
INFORMATION GATHERING	180
ESTIMATING FORMULAS	183
GUIDE TO ESTIMATING MAN-HOUR RATES	185

## Appendix F

COURSING AND LAYOUT TABLES	189
VERTICAL COURSING CHART	190
LAYOUT TABLES	191

## Appendix G

LINTEL DESIGN	197
INTRODUCTION	198
G.1 LINTEL DESIGN – US	199
G.2 LINTEL DESIGN – CANADA	208

## Appendix H

TEAR OUT AIDS	221
CONCRETE PRE-PLACEMENT CHECKLIST	223
CONCRETE POST-PLACEMENT CHECKLIST	224
CORNER FURRING TAB MARKING TEMPLATE	225

## CONTENTS

---

### List of Tables

1.0	ARXX™ PRODUCT PACKAGING	7
1.1	REINFORCING BAR DESIGNATION & SIZE	30
1.2	MINIMUM NUMBER OF SCREWS REQUIRED TO TRANSFER TEST PRESSURES SPECIFIED IN CAN/CSA A440-M90	38
1.3	MINIMUM NUMBER OF SCREWS REQUIRED TO TRANSFER TEST PRESSURES FOR WINDOWS WITH MANDATORY AAMA/NWWDA 101/1.S.2-97 RATINGS	38
1.4	MINIMUM NUMBER OF SCREWS REQUIRED TO TRANSFER TEST PRESSURES FOR WINDOWS WITH AAMA/NWWDA 101/1.S.2-97 OPTIONAL PERFORMANCE GRADES	39
6.0	AIR BARRIERS PERMEABILITY RATINGS	128
7.1.13.1	MAXIMUM EXTERNAL CONNECTION FORCES – IMPERIAL	138
7.1.13.2	MAXIMUM EXTERNAL CONNECTION FORCES – METRIC	138
7.2.1.1	BMAS NEW/OLD DESIGN COMPARISON	143
7.2.1.2	POLE EXTENSION/ANGLE RANGE	145
7.3.2.1	PARTS LIST FOR TMAS	150
E.1	ESTIMATING FORMULAS	183
E.2	CONCRETE ESTIMATING	184
E.3	MAN-HOUR RATE	185
E.4	MAN-HOUR PROJECT EXAMPLE	186
F.1	VERTICAL COURSING CHART	190
F.2	4" ARXX PREFERRED WALL DIMENSIONS	191
F.3	6" ARXX PREFERRED WALL DIMENSIONS	192
F.4	8" ARXX PREFERRED WALL DIMENSIONS	193
F.5	10" ARXX PREFERRED WALL DIMENSIONS	194
F.6	6" ARXX FIXED 45° FORM PREFERRED DIMENSIONS	195
G.1.1	APPLICABILITY LIMITS – US	199
G.1.2	BOTTOM BAR SELECTION – MAXIMUM ALLOWABLE OPENING WIDTH FOR ARXX LINTELS IN LOAD-BEARING WALLS SUPPORTING LIGHT-FRAME ROOF ONLY	203
G.1.3	BOTTOM BAR SELECTION – MAXIMUM ALLOWABLE OPENING WIDTH FOR ARXX LINTELS IN LOAD-BEARING WALLS SUPPORTING LIGHT-FRAME SECOND STORY AND ROOF	204
G.1.4	BOTTOM BAR SELECTION – MAXIMUM ALLOWABLE OPENING WIDTH FOR ARXX LINTELS IN LOAD-BEARING WALLS SUPPORTING ARXX SECOND STORY AND LIGHT-FRAME ROOF	205
G.1.5	MINIMUM STIRRUP REQUIREMENTS FOR END DISTANCE 'A' ARXX LINTELS IN TABLES G.1.2, G.1.3 AND G.1.4	206
G.1.6	MAXIMUM ALLOWABLE OPENING WIDTHS AND MINIMUM STIRRUP REQUIREMENTS FOR ARXX LINTELS IN GABLE END (NON-LOAD-BEARING) WALLS NO. 4 TOP AND BOTTOM BAR SIZE	206
G.2.1	APPLICABILITY LIMITS – CANADA	208
G.2.2	MINIMUM VERTICAL REINFORCING PER TRIBUTARY WALL LENGTH (TWL)	213
G.2.3A	BOTTOM BAR CHART FOR 1 STORY HOUSE OR TOP FLOOR OF 2 STORY HOUSE – MAXIMUM BUILDING WIDTH 24' (7.32M)	214
G.2.3B	BOTTOM BAR CHART FOR BOTTOM FLOOR OF 2 STORY HOUSE – MAXIMUM BUILDING WIDTH 24' (7.32M)	215
G.2.4A	BOTTOM BAR CHART FOR 1 STORY HOUSE OR TOP FLOOR OF 2 STORY HOUSE – MAXIMUM BUILDING WIDTH 40' (12.2M)	216



## List of Tables (cont'd)

G.2.4B	BOTTOM BAR CHART FOR BOTTOM FLOOR OF 2 STORY HOUSE – MAXIMUM BUILDING WIDTH 40' (12.2M)	217
G.2.5	STIRRUP REQUIREMENTS AND SPACING FOR LINTELS SUPPORTING ROOF ONLY	218
G.2.6	STIRRUP REQUIREMENTS AND SPACING FOR LINTELS SUPPORTING 1 STORY & ROOF	219

## List of Figures

1.1	STEP FOOTINGS	3
1.2	SQUARING FOUNDATIONS	4
1.3	MANEUVERING BUNDLES	5
1.4	LEFT-HAND AND RIGHT-HAND CORNERS & ARXX LOK	9
1.5	STANDARD FORM UNIT	12
1.6	90° CORNER FORM UNIT	13
1.7	ASSEMBLED ADJUSTABLE CORNERS	14
1.8	ADJUSTABLE CORNER FORM UNIT	15
1.8.1	ASSEMBLING ADJUSTABLE FORMS	15
1.8.2	FIXED 45° FORM	16
1.9	EXTENDED BRICK LEDGE FORM UNIT	17
1.10	MITERED BRICK LEDGE	18
1.11	MITERED 6" BRICK LEDGE	18
1.12	MITERED 8" BRICK LEDGE	19
1.13.1	TAPERED TOP FORM UNIT	20
1.13.2	BURIED WEB STANDARD FORM	21
1.14	HEIGHT ADJUSTER	22
1.15	END CAP	23
1.16	TYPICAL GRADE BEAM ON PILES	24
1.17	ASSEMBLY OF TEE-WALLS	25
1.18	4" REINFORCING	27
1.19	6" REINFORCING	28
1.20	8" REINFORCING	28
1.21	10" REINFORCING	29
1.22	BUCK SAVER™ PROFILE	31
1.23	TYPICAL BUCK SAVER INSTALLATION	32
1.24	BUCK SAVER HEAD SUPPORT OPTIONS	33
1.25	RADIUS TOP OPENINGS	35
1.26	TYPICAL DOOR INSTALLATION WITH BUCK SAVER	36
1.27	DOOR INSTALLATION WITH MASONRY VENEER	36
1.28	TYPICAL HEAD DETAIL WITH STUCCO	37
1.29	METHOD 1	42
1.30.1	METHOD 2	43
1.30.2	TYPICAL DOOR INSTALLATION WITH WOOD BUCK	43

## CONTENTS

---

### List of Figures (cont'd)

1.31	CUTTING FOR SERVICE PENETRATIONS	47
1.32	COMPRESSIVE STRENGTH OF CONCRETE	50
1.33	HOMEMADE TROWEL	54
1.34	TYPICAL WATERPROOFING DETAIL	57
1.35	WATERPROOFING MEMBRANE INSTALLATION	59
1.36-46	THE MAXX™ FOUNDATION WRAP	62
1.47	BELOW GRADE MOISTURE PROTECTION	74
3.1	EIFS APPLICATION	87
3.2	STUCCO APPLICATION	87
3.3	USE OF TAPERED TOP FORM	88
3.4	USE OF EXTENDED BRICK LEDGE FLOOR ATTACHMENT 1	89
3.5	USE OF EXTENDED BRICK LEDGE FLOOR ATTACHMENT 2	90
3.6	FASTENING AT 90° CORNERS	91
4.1	PLATFORM FRAMING	96
4.2	WOOD FRAME AND BRICK VENEER	97
4.3	EMBEDDED FLOOR JOIST	98
4.4	LEDGER BOARD CONNECTION	100
4.5	LEDGER CONNECTOR SYSTEM	101
4.5.1	LEDGER CONNECTOR INSTALLATION	102
4.5.2	ALTERNATIVE LEDGER CONNECTOR	102
4.5.3	LEDGER CONNECTOR	103
4.6	WOOD FLOOR TRUSS CONNECTION	104
4.7	TYPICAL HAMBRO® FLOOR CONNECTION	105
4.8	TYPICAL COMPOSITE DECK FLOOR	106
4.9	TYPICAL COMPOSITE DECK FLOOR	107
4.10	TYPICAL PRE-CAST DECK DETAIL	108
4.11	TYPICAL PRE-CAST DECK DETAIL	109
4.12	TYPICAL GABLE END	110
4.13	ALTERNATIVE GABLE END	110
4.14	TYPICAL CHIMNEY CONSTRUCTION	111
4.15	TYPICAL RAFTER ROOF CONNECTION	112
4.16	TYPICAL RAFTER ROOF CONNECTION WITH HURRICANE STRAPS	113
4.17	TYPICAL FLAT ROOF CONNECTION	114
4.18	CABINET ATTACHMENT	115
4.19	ALTERNATIVE CABINET ATTACHMENT	115
5.1	ELECTRICAL BOX 4" FORM	119
5.2	METER ASSEMBLY MOUNTING	121
6.1	CAVITY WALL SYNDROME	126
6.2	ARXX™ CONCRETE WALL EFFECT ON AIR PASSAGE	126
7.1	MODEL R-100 ASSEMBLY, 100 1/4" WALL (6 COURSES)	133
7.2	MODEL C-120 ASSEMBLY, 120" WALL (7 COURSES)	134



---

## List of Figures (cont'd)

7.3	MODEL C-144 ASSEMBLY, 142" WALL (8.5 COURSES)	135
7.4	FASTENER REQUIREMENTS, MODEL R-100: 100 1/4" WALL (6 COURSES)	139
7.5	FASTENER REQUIREMENTS, MODEL C-120: 120" WALL (7 COURSES)	140
7.6	FASTENER REQUIREMENTS, MODEL C-144: 142" WALL (8.5 COURSES)	141
7.7	BMAS OLD AND NEW DESIGNS	143
7.8	DIAGONAL POLE CONNECTION	144
7.9	ACCEPTABLE ANGLES	146
7.10	SCAFFOLDING ASSEMBLY	147
7.11	TMAS	151
7.12	TMAS PLAN VIEW	152
7.13	TMAS SCAFFOLD BRACKETS	153
7.14	TMAS ATTACHMENT	154
7.15	TMAS ADJUSTABLE BRACE CONNECTION	155
7.16	TMAS SCAFFOLD BRACKET CONNECTION	155
E.1	OVERLAP OF DIMENSIONS	180
G.1.1-2	LINTEL DESIGN – US	202
G.2.1-4	LINTEL DESIGN – CANADA	211-212

